Standard Construction

River Run Cabinetry's Standard Construction offers many features which are considered upgrades in other lines of cabinetry.



CASE

- Traditional face frame construction using select birch.

 Face frames are solid 3/4" thick with 1-1/2" stiles and rails.

 Mortise and tenon joints.
- 2 Sides are birch veneered 1/2" plywood. The interior features a clear-coat finish and the exterior is stained to match the door. (Hampton interior is painted soft white.)
- 3 Shelves are 5/8" thick birch veneered plywood sealed with a clear-coat finish, adjustable and front edge banded.
- For ease of installation, backs are framed with a 1/2" plywood hanging rail. Base cabinet backs extend to the floor providing optimal structural stability.

DRAWERS

5/8" thick solid hard wood, dovetail joints and clear-coated.

Bottoms are 1/4" birch plywood fully captured. Slides are under mount, full extension soft-close.

DOORS

6 Premium full overlay door styles.

Butt doors on all sizes up to 39" wide.

HINGES

7 Hinges are 6-way adjustable.

ROLL TRAYS

Optional roll trays.

All wood dovetail construction.